

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

AUG 26 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. ~~Duke~~ Mack Oil Co. of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. ~~Duke~~ guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Co.
~~Duke Drilling Company~~

Complete Address: 812 Union Center Wichita, Kansas
~~Box 823 Great Bend, Kansas~~

Lease Name: Butler Well No. # 1

Location: C SE ^{NE} Sec. 33 Twp. 25S Rge. 21 (E) (W)

County Ford Total Depth 4880' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Duke was instructed to plug the well as follows:

8 5/8"-268' Circulated w/cement. 4 1/2"-4880' Cemented.

Plug back to 4776' Top perforations 4715'

Plug bottom w/sand 4776' to 4700' 5 Sax.cement 4700' to 4640'

Mud 4640' to 500' 25 Sax.cement 500' to 425'

Mud 425' to 250' 25 Sax.cement 250' to 175'

Mud 175' to 50' Rock Bridge 50' to 40'
15 Sax.cement 40' to surface. Very truly yours,

Hugh Scott
 Conservation Division Agent