

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clifft of Amerex has this

date requested permission to plug the following described well:

Mr. Clifft guarantees payment of the plugging fee.Operator's full Name: Amerex Inc.Complete Address: 2000 Classen Center, Oklahoma City, OklahomaLease Name: Butler Well No. 6Location: C NE NE Sec 33 Twp. 25 Rge. 21 (E) (W)County: Ford Total Depth 4358' Oil Well XGas Well Input Well SWD Well D & A X Lost Hole Mr. Clifft was instructed to plug the well as follows:

8 5/8" to 198' circulated w/ cement. 4 1/2" to 4358' cemented.

Top perforations 4201' Plug bottom w/ 20 sacks cementTop of cement 3900' Mud 3900' to 200'Spot 35 sacks cement 200' to 100' Mud 100' to 45'Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edmund J. Eves
Conservation Division Agent