

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202


Dear Sir:

Mr. Cliff of Amerex has this

date requested permission to plug the following described well:

Mr. Cliff guarantees payment of the plugging fee.Operator's full Name: Amerex Inc.Complete Address: 2000 Classen Center, Oklahoma City, OklahomaLease Name: Butler Well No. 2Location: C NW NE Sec. 33 Twp. 25 Rge. 21 (E) (W)County: Ford Total Depth 4260' Oil Well XGas Well Input Well SWD Well D & A X Lost Hole Mr. Cliff was instructed to plug the well as follows:8 5/8" to 206' circulated w/ cement. 4 1/2" to 4260' cemented.Top perforations 4213' Plug bottom w/ 20 sacks cement.Top of cement 3900' Mud 3900' to 200'Spot 35 sacks cement 200' to 100' Mud 100' to 45'Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,



Conservation Division Agent