

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 29 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clift of Amerex has this

date requested permission to plug the following described well:

Mr. Clift guarantees payment of the plugging fee.

Operator's full Name: Amerex Inc.

Complete Address: 200 N. Harvey, Oklahoma City, Oklahoma

Lease Name: Torline Well No. 1

Location: C NW SE Sec. 33 Twp. 25 Rge. 21 (E)(W)

County: Ford Total Depth 4260' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Clift was instructed to plug the well as follows:

8 5/8" to 198' circulated w/ cement. 4 1/2" to 4233' cemented.

Top perforations 4203' Plug bottom w/ 20 sacks cement.


Top of cement 4100' Mud 4100' to 700'

Spot 35 sacks cement 700' to 600' Mud 600' to 200'

Spot 35 sacks cement 200' to 100' Mud 100' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

  
Conservation Division Agent