

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

RECEIVED  
 STATE CORPORATION COMMISSION  
 8-27-62  
 AUG 27 1962

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Duke of Duke Drilling Company has this  
 date requested permission to plug the following described well:

Mr. Duke guarantees payment of the plugging fee.

Operator's full Name: Mack Oil  
Duke Drilling Company

Complete Address: 812 UNION CENTER WICHITA, KAN.  
Box 823 - Great Bend, Kansas

Lease Name: Torline Well No. # 1

Location: C NW SW Sec. 34 Twp. 25S Rge. 21 (E) (W)

County Ford Total Depth 4786' Oil Well X

Gas Well      Input Well      SWD Well      D & AX      Lost Hole     

Mr. Duke was instructed to plug the well as follows:

8 5/8"-193' Circulated w/cement. 4 1/2"-4785' Cemented.

Plug back to 4777' Top perforations 4708'

Plug bottom w/sand 4777' to 4700' 5 Sax.cement 4700' to 4640'

Mud 4640' to 500' 25 Sax.cement 500' to 425'

Mud 425' to 175' 25 Sax.cement 175' to 100'

Mud 100' to 50' Rock bridge 50' to 40'

15 Sax.cement 40' to surface.  
Cut surface pipe off 3' below  
ground level. Weld on cap.

Very truly yours,

*Hugh Scott*  
 Conservation Division Agent