

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 16 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Blevins of Jones & Gebert Oil Co. has this date requested permission to plug the following described well:

Mr. Blevins guarantees payment of the plugging fee.

Operator's full Name: Jones & Gebert Oil Co.

Complete Address: 205 Central Bldg. Wichita, Kansas

Lease Name: Imel Well No. #1

Location: C NW SE Sec. 17 Twp. 25S Rge. 22 (E) (W)

County Ford Total Depth 4881 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Blevins was instructed to plug the well as follows:


8 5/8" 222' Circulate w/cement.

Mud 4881' to 500' Spotted 20 Sax.cement 500' to 440'

Mud 440' to 200' Plug, Hulls, 20 Sax.cement 200' to 140'

Mud 140' to 40' Plug, Hulls, 10 Sax.cement 40' to surface.

Very truly yours,


 Conservation Division Agent