

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

R
VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Branum of Terrel Drilling & Producinas this date requested permission to plug the following described well:

Mr. Branum guarantees payment of the plugging fee.

Operator's full Name: Terrel Drilling & Producing

Complete Address: Russell, Kansas

Lease Name: Maskus Well No. # 1

Location: C NW NW Sec. 1 Twp. 25 Rge. 25 (E) (W)

County Ford Total Depth 4850' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Branum was instructed to plug the well as follows:

8 5/8" - 275' Circulated w/cement.

Mud 4850' to 500' Hulls, 25 Sax. cement 500' to 425'

Mud 425' to 250' Hulls, 25 Sax. cement 250' to 175'

Mud 175' to 40' Hulls, 15 Sax. cement 40' to surface.

Very truly yours,

Hugh Scott
Conservation Division Agent