

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 13 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. B. Y. Newman of J. E. Newman has this

date requested permission to plug the following described well:

Mr. Newman guarantees payment of the plugging fee.

Operator's full Name: J. E. Newman

Complete Address: Suite 2005 Tower Bldg., Denver, Colorado

Lease Name: Mayhew Well No. # 1

Location: SW SW SW Sec. 28 Twp. 25 Rge. 16 (E) (W) W

County Edwards Total Depth 4500 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Newman was instructed to plug the well as follows:

420' of 8 5/8" surface pipe, cement circulated with 350

sacks. 4498' of 5 1/2" long string, cemented with 250 sacks.

Plugged back to 4470'. Perferated 4393' to 98'. Sand to

4380', cement with 3 sacks. Fill hole with mud to 225',

10' rock bridge, cement with 20 sacks. Fill hole with mud

to 40', 10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Audie Elving  
 Conservation Division Agent