

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 10 TWP. 29S RGE. 14 E/W
Location as in quarters or footage from lines:
NE NE SE

Lease Owner Vincent Oil Corporation
 Lease Name Kerr Estate Well No. #2
 Office Address 125 N. Market
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 6-17-83
 Application for plugging filed 6-17-83
 Plugging commenced 6-17-83
 Plugging completed 6-17-83
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 4720'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	412'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 1st plug @ 1050', Spotted 50 sx. cement thru drill pipe.
- 2nd plug @ 450', Spotted 50 sx. cement thru drill pipe.
- Bridge plug @ 40', Spotted 10 sx. cement thru drill pipe.
- Spotted 15 sx. cement in rathole.
- Spotted 5 sx. cement in water well.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.
Ernest Sifford (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
401 E. Douglas #500 Wichita
(Address) Kansas 67202

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 83

My Commission expires:  David F. Jamis
David F. Jamis ----- Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
7-1-83
JUL 01 1983
CONSERVATION DIVISION
Wichita, Kansas



WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Vincent Oil Corporation 125 N. Market - Suite 1110 Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Kerr Estate Well No. #2

Sec. 10 T. 29S R. 14W Spot NE NE SE

County Pratt State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 412' with 325 sx. 3%cc
2%gel

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4720'

Drilling Commenced 6-7-83 Drilling Completed 6-17-83

Formation	From	To	Tops
Cellar	0	7	
Lime, Shale	7	1552	
Sand, Shale	1552	2047	
Shale, Lime	2047	2382	
Lime, Shale	2382	3843	
Shale, Lime	3843	4150	
Lime, Shale	4150	4586	
Sand	4586	4602	
Lime, Shale	4602	4690	
Lime	4690	4720	

RECEIVED
STATE CORPORATION COMMISSION

JUL 01 1983

CONSERVATION DIVISION
Wichita, Kansas