

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21993-00-00

LEASE NAME MOSS

WELL NUMBER 1

990 Ft. from S Section Line

3040 Ft. from E Section Line

SEC. 10 TWP. 29S RGE. 14 or (W)

COUNTY Pratt

Date Well Completed 5-21-90

Plugging Commenced 5-30-90

Plugging Completed 5-30-90

COPY

RCD-6-19-90

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 100 N. Main, Suite 500, Wichita, KS 67202

PHONE# (316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-29-90 (date)

by Dan Goodrow Dodge City District (KCC District Agent's Name).

Is ACO-1 filled? No If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size 8 5/8	Put in 380.18	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
1st plug from 900' to 700' w/50 sx; 2nd plug from 400' to 240' w/40 sx; 3rd plug from 40' to surface w/10 sx; 15 sx in rathole; 10 sx in mousehole and 10 sx in water well. Total 135 sx 60/40 pozmix 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vincent Oil Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 90

Susan M. Williams
Notary Public

Commission Expires: 8/15/92

K C C

ABERCROMBIE DRILLING, INC.

801 UNION CENTER
WICHITA, KANSAS 67202

DRILLER'S WELL LOG

Vincent Oil Corporation
Moss #1
App. NE SE SW
Sec. 10-29S-14W
Pratt County, Kansas

05-21-90	9:15 p.m. to 11:00 p.m.	0 to 220 220 to 245	Top soil and sand Red Beds
05-22-90	11:00 p.m. to 1:00 a.m. 11:45 a.m. to 12:00 a.m. 3:30 p.m. to 4:15 p.m. 4:30 p.m. to 11:00 p.m.	245 to 385 385 to 840 840 to 852 852 to 875 875 to 1565	Red Beds Shale and Clay Shale and Shells Anhydrite Shale and Shells
05-23-90	11:15 p.m. to 4:00 a.m. 6:00 a.m. to 7:00 a.m. 7:00 a.m. to 11:00 p.m.	1565 to 1995 1995 to 2043 2043 to 2643	Shale Lime and Shale Lime and Shale
05-24-90	11:00 p.m. to 11:00 p.m.	2643 to 3384	Lime and Shale
05-25-90	11:00 p.m. to 11:00 p.m.	3384 to 4020	Lime and Shale
05-26-90	11:00 p.m. to 11:00 p.m.	4020 to 4490	Lime and Shale
05-27-90	11:00 p.m. to 11:00 p.m.	4490 to 4574	Lime and Shale
05-28-90	10:00 a.m. to 10:30 a.m. 8:00 p.m. to 8:30 p.m. 9:30 p.m. to 11:00 p.m.	4574 to 4582 4582 to 4607	Lime Lime and Shale
05-29-90	11:00 p.m. to 12:45 a.m.	4607 to 4670 4670 to 4675	Lime and Shale Lime Rotary Total Depth
05-30-90	plugged and abandoned		

STATE OF KANSAS
JUN 19 1990
GEOLOGICAL SURVEY
WICHITA, KANSAS