

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21480-00-00

LEASE NAME KERR

WELL NUMBER #2

SPOT LOCATION 1100' FSL E,
250 FEL SE/4
SEC. 24 TWP 29S RGE. 14W (E) or (W)

COUNTY PRATT

Date Well Completed 10-25-84

6:30 P.M.

Plugging Commenced 10-25-84

8:30 P.M.

Plugging Completed 10-25-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RISEDEN, LTD.

ADDRESS 8 GREENWAY PLAZA, 1300 CASHCO PLAZA
HOUSTON, TEXAS 77046

PHONE # () OPERATORS LICENSE NO. _____

Character of Well DRY HOLE
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? PAUL LUTHI DODGE CITY, KANSAS

Is ACO-1 filed? _____ If not, is well log attached? LOG IS ATTACHED

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	<u>8 5/8"</u>	<u>0</u>	<u>249'</u>	<u>J-55</u>	<u>6 Jts.</u>	<u>New 23 Wt.</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Well plugged as follows:

140 sks. 60-40 poz. 2% gel 3% cc.

50 sks at 1020', 50 sks at 300', 40 sks at 40', 10 sks rathole, 10 sks mousehole,

10 sks water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SUN CEMENTING

License No. _____

Address MEDICINE LODGE, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

RISEDEN, LTD.

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wayne L. Kirkman

WAYNE L. KIRKMAN
PRESIDENT

(Address) BOX 18611, WICHITA, KS. 67218

SUBSCRIBED AND SWORN TO before me this 29th day of OCT., 19 84

My Commission expires: MARCH 20, 1987

KATHLEEN G. QUINN Notary Public

Form CP-4 1-84
Revised 06-83

ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372



W E L L L O G

WELL NAME: KERR #2

WELL LOCATION: 1100' FSL 250' FEL
SE/4 SEC. 24-29S-14W PRATT COUNTY, KS.

OPERATOR: RISEDEN, LTD.

COMMENCED: 10-18-84

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMPLETED: 10-25-84

J-55 8 5/8" 23 wt. 6 jts.
CASING RECORD: new, 200 sks. common
2% gel. 3% cc. set at 249'

FORMATION:

FROM:

TO:

Red Bed-Shale

0

2005'

Lime-Shale

2005'

4350

Simpson Sand

4350'

4369'

Simpson

4369'

4433'

Simpson-Arbuckle

4433'

4475'

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1984

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED

1100' FSL & 250' FEL SE/4, SEC. 24-29S-14W, PRATT COUNTY, KANSAS TO THE BEST OF MY

KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.

Wayne L. Kirkman
WAYNE L. KIRKMAN
PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29TH DAY OF OCTOBER, 1984

KATHLEEN G. QUINN

MY APPOINTMENT EXPIRES MARCH 20, 1987

Sedgwick County, Kansas

My Appt. Exp. 3-20-87

Kathleen G. Quinn
KATHLEEN G. QUINN