

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt

County. Sec. 24 Twp. 29S Rge. 14 (W)

Location as "NE/CNW/SW" or footage from lines C - SE NE SE

Lease Owner Monsanto Chemical Company

Lease Name Andrews "B" Well No. 1

Office Address P. O. Box 580, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed 8-17-19 44

Application for plugging filed 8-16-19 60

Application for plugging approved 8-18-19 60

Plugging commenced 8-20-19 60

Plugging completed 8-26-19 60

Reason for abandonment of well or producing formation Well had reach its economic limit.

If a producing well is abandoned, date of last production August 16 19 60

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel

Producing formation Simpson Depth to top 4393' Bottom 4431' Total Depth of Well 4431 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	545'	None
				6-5/8"	4429'	2706'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4431' and found it clear.
Ran sand to 4375' and dumped 4 sacks of cement with dump bailer. Pulled 6-5/8" casing. Mudded hole to 300'. Set 10' rock bridge to 290' and ran 25 sacks of cement. Mudded hole to 40'. Set 10' rock bridge to 30' and ran 15 sacks of cement to base of cellar. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION
9-6-60
SEP 6 1960
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF KANSAS COUNTY OF PRATT, ss.
Bruce E. Roll (employee of owner)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce E. Roll

P. O. Box 580, Pratt, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of September, 19 60

Notary Public

My commission expires September 4, 1962



Casing Record.
10" 531'
6" 4396'

Andrews No. 1. Center SE/4 NE/4 SE/4 24-29S-14W
Pratt County, Kansas.

Company Carter Oil Company
Contractor J. B. Hinkle Drilling Company.

Well comm. June 7, 1944 Completed July 10, 1944.

0	212	Sand
212	445	Red rock
445	805	Red rock and shells
805	1080	Shale and salt
1080	1380	Shale and shells
1380	1410	Lime
1410	2085	Lime and shale
2085	2130	Lime
2130	2245	Lime and shale
2245	2350	Lime
2350	2385	Lime and shells
2385	2445	Lime
2445	2565	Shale and shells
2565	2600	Lime
2600	2965	Lime and shells
2965	3060	Lime
3060	3110	Shale and shells
3110	3145	Lime
3145	3190	Shale
3190	3370	Lime
3370	3380	Broken Lime
3380	3465	Lime
3465	3490	Broken Lime
3490	3550	Lime
3550	3645	Broken Lime
3645	3770	Lime
3770	3850	Lime shells
3850	3967	Shale
3967	4220	Lime
4220	4262	Lime and shale
4262	4378	Lime
4378	4385	Conglomerate
4385	4396	Shale
4396	4406	Sand T.D.
4406	4431	Oil sand

Tops:

Douglas Sand	3795
Lansing	3927
Simpson	4389

State of Kansas)
County of Sedgwick) SS

I hereby certify that the above is a true and correct log
as compiled from the daily drilling reports kept at said well.

Subscribed to before me this 24th day of July, 1944.

My commission expires 1-17-46

J. B. Hinkle
Merriel A. Lupton