

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 24 TWP. 29S RGE. 14W E/W
Location as in quarters or footage from lines:
NW SW NW

Lease Owner Antares Oil Corporation
Lease Name Chastain #1 Well No. _____
Office Address 1667 Cole Blvd. Suite 210 Golden, Colorado 80401
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed XXXXXX
Plugging commenced XXXXXX 1-25-82
Plugging completed 1-28-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom _____ T.D. 4403'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	456'	none
				4-1/2"	4402'	1755'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

~~Made bottom hole plug back with sand to 4100' and ran 4 sacks cement. Shot casing @1825' and 1745' and pulled a total of 43 joints of pipe. Plugged well with 15 sacks gel, 6 sacks hulls, 10 sacks gel, released plug and displaced with 150 sacks common cement, 4% gel, 3% cc. Plugging Complete.~~

RECEIVED
STATE CORPORATION COMMISSION
FEB - 1 1982
CONSERVATION DIVISION
Wichita, Kansas
02-01-82

(If additional description is necessary, use _____ this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 82



Irene Hoover
Notary Public.

My Commission expires: _____

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Chastain #1
 100' S of NW-SW-NW
 Sec 24-29S-14W

Pratt County Kansas

Commenced: 8-2-81

Completed: 8-15-81

OPERATOR: ANTARES OIL CORP.

Depth		Formation	Remarks
From	To		
0	463	Sand-Shale	
463	1267	Redbed-Shale	Ran 11 jts of 24# 8 5/8" csg
1267	2607	Shale	set @ 459 Cemented w/
2607	3063	Shale-Lime	300 sks 40/40 Posmix
3063	3375	Lime-Shale	2% Gel - 3% CC
3375	4410	Lime	PD @ 1:45 a.m. 8-3-81
	4410 - TD		RAn 108 jts of 10 1/2# 4 1/2"
			csg set @ 4403' Cemented
			w/250 sks 60/40 Posmix
			10% Salt - 10# Gilsomite
			per sack - 3/4 of 1% CFR-2
			PD @ 11:30 a.m. 8-15-81

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief and
 according to the records of this office.

GABBERT-JONES, INC.

[Signature]
 JAMES S. SUTTON II

Subscribed and sworn to before me this 18th day of August, 1981.

[Signature]
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 14 1981
 CONSERVATION DIVISION
 Wichita, Kansas

