

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,359

LEASE NAME Kerr

WELL NUMBER #1

SPOT LOCATION NW NE SE

SEC. 24 TWP. 29 RGE. 14 (E) or (W)

COUNTY Pratt

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-22-86

Plugging Completed 3-31-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Risden Ltd.  
ADDRESS c/o Sharp Eng. Oil Operations  
708 One Main Place  
Wichita, Kansas 67202  
PHONE # (316) 721-2638 OPERATORS LICENSE NO. 9171

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One (1)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4504'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	298'	None
				5-1/2"	4503'	3,368.01'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 4375' and 5 sacks cement. Shot casing at 3400'. Pulled 85 jts. of 5-1/2": Halliburton squeezed well with 4 sacks hulls, 10 sacks gel, 50 sacks cement, 5 sacks gel, and 120 sacks light cement. Maximum pressure was 450 psi and shutin 375 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111  
Address Box 698, Gt. Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
(Address) James W. Rockhold  
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 1st day of April, 1986



IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-87

Iona M. Leatherman  
Notary Public

My Commission expires:

RCD 4-2-86

APR - 2 1986

CONSERVATION DIVISION