


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202.

Pratt County, Sec. 24 Twp. 29S Rge. 14W
Location as "NE/CNW/SW" or footage from lines



Locate well correctly on above Section Plat

Lease Owner Antares Oil Corporation
Lease Name Kiley Well No. 1
Office Address 1667 Cole Blvd. Suite 210 Golden, Colo.
Character of Well (Completed as Oil, Gas or Dry Hole) 80401

Oil well
Date Well completed 9-20-79
Application for plugging filed 7-22-82
Application for plugging approved July 26, 1982
Plugging commenced Oct. 11, 1982
Plugging completed Oct. 13, 1982
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last product:

Was permission obtained from the Conservation Division
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bud Metz Stafford, Kansas
Producing formation Mississippian Depth to top 4200 Bottom 4720 Total Depth of Well 4720
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Bed		0'	493'	8 5/8"	493'	0'
Mississippian		0'	4720'	4 1/2"	4719'	2025'

Describe in detail the manner in which the well was plugged, indicating where the plug was placed and the method or methods used in introducing it into the hole. If cement or plugs were used, state the character of same and depth placed, from 4719' feet to 4573' feet for each plug set, of frac sand with 4 sx of common cement on top of sand. Top of cement plug would be approx. 4520'. Dia log shot 4 1/2" casing off at 2025' and pulled out of hole. Halco hooked up to 8 5/8" surface pipe and pumped 5 sx of hulls, 25 sx of gel, 150 sx of 50/50 sx of pox mix with 4% gel and 3% cal. Chloride. Left pressure on well Plug down at 11:00AM.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt ss.

Kenneth C. Gates (employee of owner) or (owner or agent) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth C. Gates
Box 847 Pratt, Kansas 67124-330
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of November, 1982


Charlene M. Dudley
Notary Public.

My commission expires 9/1/86



DEC 1 1982

CONSERVATION DIVISION
Wichita, Kansas



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Kiley #1
 NW-NW-NE Sec 24-29S-14W
 Pratt County Kansas

Commenced: 9-5-79

Completed: 9-20-79

OPERATOR: Antares Oil Corporation

From	Depth to	Formation	Remarks
0	215	Top Soil-Clay-Sand	Ran 12 jts of 24# 8 5/8" csg
215	283	Sand	set @ 493' Cemented w/
283	571	Shale	300 sks Common 2% Gal
571	850	Redbed	3% CC PD @ 9:45 a.m. 9-6-79
850	2506	Shale	1" w/100 sks Common
2506	3182	Shale-Lime	6% Gal
3182	3238	Lime-Shale	PD @ 1:00 p.m. 9-6-79
3238	3342	Shale-Lime	
3342	3360	Lime-Shale	
3360	3890	Shale-Lime	Ran 147 jts of 10 1/2# 4 1/2"
3890	4055	Lime	Csg set @ 4719'
4055	4200	Shale-Lime	Float @ 4696' DV Tool
4200	4720	Lime	@ 3380' Cemented w/275
	4720-TD		sks Common on Bottom Cemented through DV Tool w/300 sks 50/50 Posmix Job Complete @ 2:15 a.m. 9-20-79

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 25th day of September, 1979.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

