

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-155-21,065-2000

LEASE NAME Stroud

WELL NUMBER 1

SPOT LOCATION NE/4 NE/4 NE/4

SEC. 3 TWP. 24 SRGE. 5W (E) or (W)

COUNTY Reno

Date Well Completed 8/26/85

Plugging Commenced 8/26/85

Plugging Completed 8/26/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Associated Petroleum Consultants, Inc.

ADDRESS 600 One Main Place, Wichita, Ks. 67202

PHONE # (316) 265-9385 OPERATORS LICENSE NO. 5601

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks. 67801 - Warren Kirkpatrick

Is ACO-1 filed? yes If not, is well log attached? yes

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3,970'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4"	250.90'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug @ 3970' w/50 sx cement; 2nd Plug @ 730' w/35 sx cement;  
3rd Plug @ 400' w/35 sx cement; 4th Plug @ 40' w/15 sx cement;  
10 sx cement in rathole (Plugs calculated by displacement)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. NA  
Address Box 963, Pratt, Kansas 67124

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

I, Phyllis Buchanan (employee of operator) or  
(~~XXXXXX~~) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so HELP ME God.

STATE CORPORATION COMMISSION


(Signature) Phyllis Buchanan

(Address) Phyllis Buchanan

SEP 23 1985 9-23-85

SUBSCRIBED AND SWORN TO before me this 19 day of Sept., 1985

CONSERVATION DIVISION  
Wichita, Kansas



Jerri Castor  
Notary Public  
Jerri Castor

My Commission expires:

Cont.

DRILLERS LOG

0 - 420	Sand & Stone
420 - 885	Shale
885 - 1115	Shale & Lime
1115 - 1315	Shale
1315 - 1555	Lime & Shale
1555 - 1925	Shale
1925 - 3333	Shale & Lime
LOST CIRCULATION	
3370 - 3540	Lime & Chert
3540 - 3635	Lime
3635 - 3865	Shale & Lime
3865 - T.D.	Shale & Sand

RECEIVED  
STATE CORPORATION COMMISSION

SEP 23 1985

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 23 1985

CONSERVATION DIVISION  
Wichita, Kansas