

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 88-5

LOCATION CS40-NE 22E

SEC. 27 TWP. 25 RGE. 14-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Kipp - "A"

Operator Shelly Oil Co. Address Box #391 Hutchinson-Kans.

Field _____ County Stafford

Total Depth 3906 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 16" - 2650' - Circulated with cement
1 3/4" at 2830' - 300 sacks of cement - 8 1/2" casing set at 3680'
cemented with 100 sacks of cement. Plugged back to 3050'
with mud-cement & shot - Dumped 6 sacks of cement
at 20 000' - shot off & pulled the 8 1/2" casing - filled
hole with mud - shot off 750' of 1 3/4" casing - Set Plug
& 25 sacks of cement at 750' - mud to 300'
Bridge & 40 sacks of cement at the surface.
Beenas & Sons - Plugging Contractors*

AUG 8 X 1951 8-8-51

Conservation Division
District Conservation Agent

Date 8-6-51

PLUGGING
FILE SEC 27 T 25 R 14W
BOOK PAGE 88 LINE 5