

OCT 01 1982 STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION AGENT REPORT

API Number 15-151-21,163 ¹⁰⁰ *[Signature]*

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Seagull Operator

Complete Address 1215 Mid-South Tower Shreveport, La. 71101

Lease Name Prather Well No. 1

Location C-SW-NW-SE Sec. 12 Twp. 29 Rge. 14 (East) (West)

County Pratt Total Depth 4725'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service Inc.

Address Box 847, Pratt, Kans. 67124 License No. 25

Operation Completed: Hour: 1:15 PM Day: 28 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

5 1/2" @ 4725' plug back to 4540' + perf. at 4045' to 4460'. 1st plug from 4460' up to 3950' w 55 sbp cement. 2nd plug @ 840' w 70 sbp cement. 3rd plug at 440' w 70 sbp cement. 4th plug @ 40' to 0' w 20 sbp cement. The cement was pumped through tubing with hole full of heavy mud. The plugging was accomplished by Danwell Cementing.

Amount of Surface Casing: 8 5/8" @ 462' cement circulated w 600 sbp

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luther
Conservation Division Agent
Bob Carleton gave these orders.

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 11-15-82

INV. NO. 1639-W

153.56

