

KANSAS

R

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued October 27, 1967.

Operator's Full Name Producers Oil Company

Complete Address: 711 Philtower Bldg., Tulsa, Oklahoma 74103

Lease Name Morrell Well No. # 1

Location SW SW NE Sec. 10 Twp. 29 Rge. 14 (E) (W) W

County Pratt Total Depth 4698'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 10:45 AM Day 28th Month November Year 1967

The Above well was plugged as follows:

300' of 8 5/8" surface pipe, cemented with 225 sacks. 4696' of 5 1/2" long string,
cemented with 150 sacks. Plug back T.D. 4652'. Top perforation 4448'. Bottom of
the hole was sanded to 4400', and cemented with 5 sacks, through the dump bailer,
with cement from 4400' to 4360'. 3730' of 5 1/2" long string was recovered from the
hole. Fluid in the hole was bailed down to 290', bridge plug and rock bridge from
290' to 280', and cemented with 25 sacks, with cement from 280' to 205'. Hole
was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10
sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 11-29-67

INV. NO. 6188-W