

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 - - ✓ (of this well)

Operator's Full Name Xplor Drilling Co.

Complete Address 453 S. Webb Rd., Box 18611, Wichita, Ks. 67207

Lease Name Andrews Well No. 4

Location NE SW SE Sec. 24 Twp. 29s Rge. 14 (E) (W) X

County Pratt Total Depth 4407

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereafter indicated

Plugging Contractor Co. Tools & Russ Casing Pulling Inc.

Address Box 1082 Gt, Bend, Ks. 67530 License No. 623

Operation Completed: Hour 3:30 Day 9 Month 7 Year 1980

The Above well was plugged as follows:

Pipe pulled on this well 9-20-74. Top never plugged. 495' 10 3/4"
casing-No information on pref's-Sand back to 4200'-Mix & dump 4 sax
mixed cement on top of sand w/dump bailer. 5 1/2" casing set at 4406'-
Pull 2286' casing-Dump 8 yard grout in 10 3/4" casing from 400' back
to zero. Pratt Ready Mix.

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1980

I hereby certify that the above well was plugged as stated.
Wichita, Kansas

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 7-16-80
INV. NO. 2606-W

COPY


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas.

Company. LION OIL CO.
Farm Name. Andrews No. 4

Sec. 24 T. 29 R. 14 W
NE SW SE

Total Depth. 4408
Comm. 11-6-45 Comp. 1-23-46
Shot or Treated. 1000 gals.
Contractor.
Issued. 4-20-46

County Pratt



CASING:

10" 495'
5" 4406'

Elevation _____

Production. Phy. Pot. 269 B
plus 22% Wtr.

Figures Indicate Bottom of Formation

surface soil	10
post rock	20
sand	60
post rock	100
shale sdy	145
sand	200
red bed	265
red bed & sand	370
red bed	450
shale & shells	510
red bed	690
anhydrite	725
sand & shale	1045
shale & shells	1575
salt & shale	1660
shale & shells	1900
lime & shale stks	1970
lime	2634
shale & lime shells	2670
lime & shale	3140
lime	3842
lime & shale	3915
lime	4280
shale & lime shells	4324
lime shells & shale	4347
lime & shale	4408
Total Depth	

Tops:
Simpson 4323
Arbuckle 4405

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1974

CONSERVATION DIVISION
Wichita, Kansas