

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-155 - 20,554-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Kelso Casing Pulling

Complete Address Box 176, Chase, Ks. 67524

Lease Name Bauman Well No. # 1

Location C. SE/4 Sec. 13 Twp. 24 - SRge. 5 (~~East~~) (West)

County Reno Total Depth 3953'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Same as above License No. # 683

Operation Completed: Hour: 1:15 PM Day: 7 Month: 7 Year: 19 81

Plugging Operations attended by Agent? All X Part None

The above well was plugged as follows:

12 3/4" sur. csg. 342' cement./400 sx. 5 1/2" csg. 3953' cement./275 sx.

Perf. 3385' to 90', set plug 3360', Perf. 3356'-58', 3359'-60', set

plug 3028', perf. 2990'-91'. Sand hole 2900', dumped 4 sx. cement.

Shot & pulled 2263' 5 1/2" csg. Left 1690' csg. in hole.

Allied Cementing Co. Inc. pumped 4 sx. hulls, 20 sx. gel, 200 sx. cement.

4% gel, down 12 3/4" sur. csg. PP 600# SIP 400#

RECEIVED
STATE CORPORATION COMMISSION

14 1981 7-14-81

(Send copy to Gilbert J. Toman, Holyrood, Ks. 67450) VISION

Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: Don Thompson
Conservation Division Agent

INVOICED

DATE 8-19-81

INV. NO. 6153-4