

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-057-20, 410-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Denver-Alaska Oil Company OPERATORS LICENSE NO. 4043

ADDRESS 350 Indiana St., Ste. 410, Golden, CO 80401 PHONE # (303) 278-4814

LEASE (FARM) Torline WELL NO. 1 WELL LOCATION CNESW COUNTY Ford

SEC. 33 TWP. 25S RGE. 21 (E) or (W) TOTAL DEPTH 4872' PLUG BACK TO Surf.

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 367' CEMENTED WITH 250 SACKS

CASING SIZE N/A SET AT CEMENTED WITH SACKS

PERFORATED AT N/A

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 50 sx @ 1400', 50 sx @ 660', 40 sx @ 400',

10 sx @ 40', 15 sx in rathole; Total 165 sx 60/40 POZmix with 2% gel & 3% calcium chloride

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? yes
(If not, explain) Well logs with ACO-1

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11/08/85 P.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Allen Drilling Company (John Johnson) PHONE # (316) 793-3582

ADDRESS P.O. Box 1389, Great Bend, Kansas 67530

PLUGGING CONTRACTOR Allen Drilling Company LICENSE NO. 5418

ADDRESS P.O. Box 1389, Great Bend, Kansas 67530 PHONE # (316) 793-3582

PAYMENT WILL BE GUARANTEED BY OPERATOR ~~OR AGENCY~~ SIGNED: Ann J. Donnelly
Denver-Alaska Oil Company (Operator ~~OR AGENCY~~)

1-6-86

JAN 6 1986 DATE: 12/31/85