

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 6 Twp. 25S Rge. 11W E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines
NE NE SE


Lease Owner Beran Corporation
Lease Name Wilson #1 Well No. 1
Office Address 970 Fourth Financial Center, Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed August 27, 1979 19'
Application for plugging filed August 26, 1979 19'
Application for plugging approved August 26, 1979 19'
Plugging commenced 3:00 AM August 27, 1979 19'
Plugging completed 5:15 AM August 27, 1979 19'
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4415'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	322'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

9-5-79
Filled hole with heavy mud.
Plugged with 40 sacks at 540';
40 sacks at 300'; 10 sacks 0 to 40';
3 sacks in rathole and 2 sacks in mousehole.

RECEIVED
STATE CORPORATION COMMISSION

SEP - 5 1979

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
STERLING DRILLING COMPANY
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of August, 1979.



My commission expires

Charles M. Hall
Charles M. Hall, Notary Public.

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - TILSON #1
Located: NE 1/4, Section 6-25E-14N, Stafford County,
Kansas

OWNER: Peren Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 17, 1979
COMPLETED: August 27, 1979

TOTAL DEPTH: 4415'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 160 Sand	Ran 7 joints, 8 5/8" used casing, 310.5' set at 322' K.B. Cemented with 225 sacks 60/L0 Fozmix with 3" cc. Plug down at 3:45 AM, 8-18-79.
160 - 1840 Shale	
1840 - 3970 Lime and Shale	
3970 - 3981 Lime	
3981 - 4400 Lime and Shale	
4400 - 4415 Lime	Plugged.

Deviation Surveys: 3/4° at 300'
3/4° at 3981'
1° at 4193'

RECEIVED
STATE CORPORATION COMMISSION

SEP - 5 1979

CONSERVATION DIVISION
Wichita, Kansas