


STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 7 TWP. 25S RGE. 14W ~~E/W~~
Location as in quarters or footage from lines:
NE NW SW



Locate Well
correctly on above
Section Platt..

Lease Owner Nadel and Gussman
Lease Name SUITER 'B' Well No. #1
Office Address 3232 First National Tower-Tulsa, OK 74103
Character of Well (Completed as Oil, Gas or Dry Hole): Oil (converted to SWD)
Date Well Completed 5/26/66
Application for plugging filed September 17, 1982
Plugging commenced October 8, 1982
Plugging completed October 8, 1982
Reason for abandonment of well or producing formation _____
Condition of Casing _____

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation Arbuckle/Lansing Depth to top 3800 bottom 4243 T.D. 4243

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Arbuckle/Lansing KC (co-mingled)	saltwater	3800	4243	5-1/2"	4243	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Circulated 100 sacks 50/50 Poz, 4% gel, 3% CaCl, down 2-1/2" tubing and filled to surface; then pumped 100 sacks (mixed as above) down between 5-1/2" and 8-5/8" and filled to surface.

10-18-82

RECEIVED
OCT 18 1982
UNDERVALUATION DIVISION
Wichita, Kansas
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing Co. Inc. (Russell, Ks.)

STATE OF Oklahoma COUNTY OF Tulsa, ss.
M. R. Taylor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M R Taylor
3232 First National Tower-Tulsa, OK 74103
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 82

Mildred Carter
Notary Public.

My Commission expires: 5/11/83

STENCILED

ORIGINAL

NOV 26 1966

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY REX & MORRIS, ETAL

SEC. 7 T. 25 N. 14W
LOC. NE NW SW

FARM Suiter "B" NO. 1

TOTAL DEPTH 4243
COMM. 5-11-66 COMP. 5-26-66
SHOT OR TREATED
CONTRACTOR Rex & Morris
ISSUED 11-26-66

COUNTY Stafford
KANSAS



CASINO

20 10
15 8 5/8" @ 320 w/ 225 SX
12 6
13 5 1/2" @ 4243' w/100 SX

ELEVATION 2021'KB

PRODUCTION FMP 50 BOFPD,NW
(Miss Chert 4230 1/2 - 34 1/2)

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Hole	320
Shale & Sand	526
Shale	1835
Lime & Shale	2643
Shale & Lime	3010
Lime	3624
Shale - Heebner	3646
Lime - Toronto	3664
Shale & Lime	3800
Lime - Kansas City	4120
Lime	4199
Lime - Mississippi Chert-RTD	4243

TOPS: SMP

Topeka	3053
Heebner	3624
Toronto	3646
Douglas Shale	3664
Lansing KC	3800
Base Kansas City	4120
Marmaton Lime	4130
Mississippi Chert	4199

STATE RECEPTION COMMISSION
RECEIVED
SEP 20 1966
CONSERVATION DIVISION
Wichita, Kansas