

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County, Sec. 9 Twp. 25 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Morris Sitrin

Lease Name Collins Well No. 1

Office Address Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 10/12/67 19

Plugging completed 10/17/67 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elving

Producing formation Depth to top Bottom Total Depth of Well 4246 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRBM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	262'	none
				5-1/2"	4246'	1673'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 4050', dumped 5 sacks of cement.
Loaded hole, shot pipe at 2997', 2730', 2523', 2224', 2031'
and 1667', pulled 55 joints. Had water truck suck down fluid in cellar.
Set 10' rock bridge at 250', dumped 5 sacks of cement. Set over night
plug. Bailed hole to 250', dumped 20 sacks of cement. Mudded to 40',
10' rock bridge and capped with 10 sacks of cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY, INC.

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 67

My commission expires February 15, 1971

Margaret Melcher
Notary Public.

RECEIVED
NOV 21 1967
11-21-67