

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Stafford County, Sec. 9 Twp. 25 Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines N/2 NE NE  
Lease Owner Alpine Drilling Co., Inc.  
Lease Name Collins Well No. 1  
Office Address 800 Bitting Building, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced August 4 19 76  
Plugging completed August 12 19 76  
Reason for abandonment of well or producing formation depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4150 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			260'	8 5/8"	260'	none
			4147'	4 1/2"	4147'	1854.60

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 4050' and dumped 4 sacks of cement.

Allied Cementing Company plugged well pumping in 3 sacks of hulls, 15 sacks of gel and 100 sacks of cement.

RECORDED  
STATE CORPORATION COMMISSION  
AUG 20 1976  
Conservation Division  
Wichita, Kansas

8-20-76

Name of Plugging Contractor PIPE PULLERS, INC.  
Address Box 128, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18th day of August, 1976

JENNY KASSELMAN  
NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
MY COMM. EXP. JULY 16, 1978

Jenny Kasselmann  
Notary Public.

My commission expires

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- COLLINS #1  
Located: NE/4, Section 9-25S-14W, Stafford County, Kansas  
(N/2 NE NE)

OWNER: Alpine Drilling Company, Inc.  
ROTARY DRILLING CONTR. CTOR: Sterling Drilling Company

COMMENCED: June 16, 1976  
COMPLETED: June 24, 1976

TOTAL DEPTH: 4150'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 133 Sand and Clay	Ran 6 joints 8 5/8", 25# used casing,
133 - 261 Shale	248.79' pipe set at 260' K.B. Cemented
261 - 874 Red Beds and Sand	with 225 sacks Regular with 2% gel and
874 - 904 Anhydrite	3% cc. Plug down at 10:00 PM, 6-16-76.
904 - 1870 Shale and Shells	
1870 - 3709 Lime and Shale	
3709 - 3830 Lime	
3830 - 3854 Lime and Shale	
3854 - 3948 Lime	
3948 - 4080 Lime and Shale	
4080 - 4125 Lime and Chert	
4125 - 4145 Shale	
4145 - 4150 Shale and Lime	Ran 102 joints new 4 1/2", 10.5# casing,
	4140.62' set at 4148' K.B. with 100 sacks
	Common cement. Plug down at 11:15 PM,
	6-24-76.