


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Russell County. Sec. 18 Twp. 12 Rge. (E) 15 (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NE SE  
Lease Owner A. C. Poole  
Lease Name Mermis Well No. #1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-9-1949  
Application for plugging filed 2-9-1949  
Application for plugging approved 2-18-1949  
Plugging commenced 2-9-1949  
Plugging completed 2-11-1949  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Box 207, Great Bend, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3332 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	940'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Surface casing in hole 940' of 8-5/8"  
Cemented from top to bottom with 450 sacks of cement.  
10 sacks of cement at 3332 feet  
Mud to 925 feet  
Bridged at 925 to 915 feet  
10 sacks of cement at 915 feet  
Mud at 200 feet  
Bridged and cemented with 10 sacks cement at 200 feet  
Mud to 20 feet  
Bridged and cemented with 10 sacks cement to surface.

RECEIVED

Conservation Div.  
02-23-49  
FEB 23 1949

STATE CORPORATION  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Stearns Petroleum, Inc.  
Address Box 313, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
O. G. Stearns (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *O. G. Stearns*

Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of February, 1949.

*B. F. Hemen*

Notary Public.

My commission expires August 17, 1950.

PLUGGING  
FILE SEC 18 T 12 R 150  
BOOK PAGE 83 LINE 30

MERMIS #1 - WELL LOG

Stearns Petroleum, Incorporated  
 Commenced: 1-13-49  
 Completed: 2-9-49

NW NE SE, Section 18-12-15N  
 Russell County, Kansas  
 Elevation: 1876 D.F.

Casing Record

8-5/8" = 94.0' Cmtd w/450 sacks.

	<u>FROM</u>	<u>TO</u>
Clay	0	35
Sand	35	70
Clay	70	238
Shale	238	300
Sand	300	405
Shale	405	495
Sand	495	535
Shale	535	650
Red rock	650	930
Lime (Anhy.)	930	982
Red rock	982	1155
Shale	1155	1360
Salt and shale	1360	1670
Lime and shale	1670	2390
Shale and shells	2390	2620
Shale	2620	2645
Lime and shale	2645	2870
Lime	2870	2945
Lime and shale	2945	3004
Lime (Kansas City)	3004	3290
Conglomerate	3290	3324
Granite	3324	3332

3332 Total Depth

STATE OF KANSAS )  
 ) ( SS:  
 COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

*[Signature]*  
 \_\_\_\_\_

Subscribed and sworn to before me this 22nd day of February, 1949.

*[Signature]*  
 \_\_\_\_\_  
 Notary Public

My Commission Expires: August 17, 1950.

PLUGGING  
 FILE SEC 22 T. 12 R. 15 W  
 BOOK PAGE 83 LINE 30

RECEIVED  
 Conservation Div.  
 FEB 23 1949  
 STATE CORPORATION  
 COMMISSION  
 KANSAS