

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County. Sec. 11 Twp. 25 Rge. 14 (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE

Lease Owner ~~Wichita~~ Welch & Olsson Drilling Co. Inc.

Lease Name Bair Well No. 2

Office Address 203 Rule Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-7 19 54

Application for plugging filed 5-7 19 54

Application for plugging approved 5-7 19 54

Plugging commenced 5-7 19 54

Plugging completed 5-7 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production March 19 54

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas

Producing formation Viola Lime Depth to top 4122 Bottom 4142 Total Depth of Well 4224 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	273'	
				5 1/2"	4227'	50'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Displaced five sacks of cement and 1000# of crushed rock inside of casing. Filled up 41' off of bottom. Displaced with service truck 100 sacks of cement on top of plug thru surface casing to surface. Plug stopped at 700' from surface.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 21 1954  
CONSERVATION DIVISION  
7-2-54

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Welch & Olsson Drilling Co. Inc.  
Address 203 Rule Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. E. Welch (employee or owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. E. Welch*  
203 Rule Bldg. Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of June, 19 54  
*Edith E. Egan*  
Notary Public.

My commission expires June 12, 1955

PLUGGING  
FILE SEC 11 T25 R4W  
BOOK PAGE 29 LINE 14

WELL LOG

WELCH & OLSSON DRILLING CO. INC.,

Elevation: 1961' R. B.

CONTRACTOR: Welch & Olsson Drilling Co. Inc.,

Commenced Drlg: 9-11-53

Bair #2

Completed Drlg: 9-28-53

NW NE NE Sec. 11-25S-14W,  
Stafford County, Kansas.

Production: 25 bbl.

casing record:

Set 272' of 8-5/8" with 225 sacks.

(Figures indicate bottom of formations)

FORMATIONS:

DEPTHS

FORMATION TOPS

Sand	135'
Shale	285'
Red Bed & Shale	862'
Anhydrite	880'
Shale	1010'
Shale & Shells	1760'
Shale & Lime	2340'
Shale & Shells	2405'
Shale & Lime	2550'
Shale & Shells	2890'
Shale & Lime	2980'
Lime & Shale	3265'
Lime	3507'
Heebner	3512'
Lime	3605'
Shale	3646'
Lime	4039'
Chert	4071'
Shale	4122'
Chert & Lime	4224' T.D.

Heebner	3507 - 1546'
Toronto	3527 - 1566'
Brown Lime	3646 - 1685'
K. C. Lans.	3677 - 1716'
Base K. C.	3964 - 2003'
Mississippian	4039 - 2078'
Kinderhook	4071' - 2110'
Viola	4122 - 2161'

STATE OF KANSAS,  
COUNTY OF SEDGWICK: SS:

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the NW NE NE of Sec. 11, Township 25S, Range 14 West, Stafford County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.,

BY: \_\_\_\_\_

R. E. Welch

Subscribed and sworn to before me this 17th day of October, 1953.

My Commission Expires: Feb. 27, 1956.

Marcella J. Davis  
Notary Public

**PLUGGING**  
FILE SEC-11-25-14W  
PAGE 29 LINE 4

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 24 1954  
CONSERVATION DIVISION  
Wichita, Kansas