


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plot

Edwards County, Sec. 8 Twp. 25S Rge. 16 K/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C NE/4

Lease Owner Penguin Petroleum, Inc.  
Lease Name English Well No. 1  
Office Address 515 Fourth Financial Center, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole)  
dry hole

Date Well completed 8/30/1982  
Application for plugging filed 8/30/1982  
Application for plugging approved 8/30/1982  
Plugging commenced 8/30/1982  
Plugging completed 8/30/1982

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durant  
Producing formation Depth to top Bottom Total Depth of Well

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Total Depth 4375 feet. Set first plug at 960 feet with 50 sacks of 50/50 poz mix cement, 4% Gel and 3% Calcium Chloride; set second plug at 480 feet with 60 sacks; a bridge and 10 sacks at 40 feet and 10 sacks in the rathole. Job completed at 12:00 p.m. on 8/30/82.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kaw Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss. contractor  
K.S. Martin, President of Kaw Drilling Co., Inc. (employer or contractor or owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

*K.S. Martin*  
K. S. Martin, President 1010 Union Center  
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 1st day of September, 1982.

My commission expires December 19, 1983  
STATE CORPORATION COMMISSION

*Mary Susan Whaley*  
Mary Susan Whaley, Notary Public.

RECEIVED  
SEP 2 1982  
CONSERVATION DIVISION  
Wichita, Kansas

MARY SUSAN WHALEY  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. \_\_\_\_\_

9-2-1982

OPERATOR:	Penguin Petroleum, Inc.
CONTRACTOR:	Kaw Drilling Co., Inc.
WELL NAME:	English #1
LOCATION:	C NE/4 Sec. 8-25S-61W Edwards County, Kansas
SPUD DATE:	August 23, 1982
COMPLETION DATE:	August 30, 1982


0	2112	Shell and Shale
2112	2362	Shale
2362	2992	Shell and Shale
2992	4226	Shale
4226	4375	Shale and Lime
	4375	R.T.D.

Spud hole at 5:00 P.M. on August 23, 1982. Drilled 457 feet of 12½ inch hole. Ran 11 joints of 8 5/8 inch, 23 pound new casing. (Tallied at 442.33 feet.) Set at 454 feet with 325 sacks of common cement, 3% Calcium Chloride and 2% Gel. Plug down at 1:15 A.M. on August 24, 1982.

Total Depth 4375 feet. Set first plug at 960 feet with 50 sacks of 50/50 poz mix cement, 4% Gel and 3% Calcium Chloride; set second plug at 480 feet with 60 sacks; a bridge and 10 sacks at 40 feet and 10 sacks in the rathole. Job completed at 12:00 p.m. on August 30, 1982.

STATE OF KANSAS        )  
  )    SS  
COUNTY OF SEDGWICK )


I, K. S. Martin, President of Kaw Drilling Co., Inc., being first duly sworn and upon my oath, state that: I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

  
K. S. Martin, President

SUBSCRIBED AND SWORN to before me on this 1st day of September, 1982.

  
Mary Susan Whaley, Notary Public

My Commission Expires:  
December 10, 1983



RECEIVED  
STATE CORPORATION COMMISSION

SEP 2 1982

CONSERVATION DIVISION  
Wichita, Kansas