

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-047-00379-0000

LEASE NAME Mantey

WELL NUMBER #4

 Ft. from S Section Line

 Ft. from E Section Line

C NE NE

SEC. 26 TWP. 25 RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 5-27-88

Plugging Completed 6-8-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR D.R. Lauck Oil Co., Inc.

221 S. Broadway, Suite 400

ADDRESS Wichita, Kansas 67202

PHONE# (316) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4486'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13-3/8"	213'	none
				5-1/2"	4466'	1626'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4285' and 5 sacks cement. Shot pipe @3000', 2500', 2300', 2100', pulled 9 joints, pipe was hung up, shot again @1436'.

Pulled a total of 50 joints of 5-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, released plug, 125 cement, 60/40 pos.,

(If additional description is necessary, use BACK of this form.) 6% gel. Plugging Complete.

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) Box 347 Chase, Kansas 67524


SUBSCRIBED AND SWORN TO before me this 21st day of June, 19 88

JUN 23 1988

Gene Hoover
 Notary Public

My Commission Expires:

CONSERVATION DIVISION
 Wichita, Kansas



6-23-1980