

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 26 TWP. 25s RGE. 16w E/W
Location as in quarters or footage from lines:
C of S/2 NE SW

Lease Owner Edwards Oil Co.
Lease Name L. S. Russell Well No. 1
Office Address P.O. Box 206 Hutchinson, KS 67501
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed 5-81
Application for plugging filed 7-2-81
Plugging commenced 12/81
Plugging completed 12/81
Reason for abandonment of well or producing formation Casing Pulled

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation Cherokee Depth to top 4332 bottom 4336 T.D. 4423'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from feet
to feet for each plug set.

1st Plug 3 4 sx
2nd Plug 4 sx hulls, 25 sx jell, 150 sx cement
Cement used was 50/50 poz, 4% gel, 3% cc
2600' pipe recovered

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1982

CONSERVATION DIVISION
Wichita Kansas

2-17-1982

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton

STATE OF Kansas COUNTY OF Reno, ss.


Keith D. Smith (~~employee of owner~~) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Hutchinson, Ks 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of January, 19 82

Keith D. Smith
Notary Public.

My Commission expires: April 28, 1984



WELL LOG

OPERATOR: Edwards Oil, Inc.

WELL NAME: Russell # 1 LOCATION: C S/2 S/2 SW 26-25S-16W

COUNTY: Edwards STATE: Kansas

WELL COMMENCED: 5-6-1981 WELL COMPLETED: 5-15-1981

ELEVATION: 2057 GL TOTAL DEPTH: 4420'

PRODUCTION: yes RIG NO: 1

CASING - 8 5/8" Run 11 Jts. of new 8 5/8, # 24., tallied 467', set @ 472'.
Cemented with 400 sx of Class A, 2% Gel, 3% CC
4 1/2" Run 106 Jts. of new 4 1/2", # 10 1/2, tallied 4429', set @
4418'. Cemented with 175 sx of 50/50 POZ, 18% Salt, 3/4#
CRF.

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0'	430'	Drift	4100' 1 1/2° off.	
430'	1490'	Sand & Shale		
1490'	2048'	Shale		
2048'	3905'	Lime & Shale		
3905'	4097'	Lime		
4097'	4237'	Lime & Shale		
4237'	4300'	Lime		
4300'	4360'	Shale & Limestone		
4360'	4379'	Shale & Lime		
4379'	4420'	Shale		

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1981
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

COUNTY OF Sedgwick

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

BIG KAT, INC.

By Ronald J. Kothel



SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 26th day of May, 19 81.

My Commission expires: 4-4-1984

Elfie A. Lacio
NOTARY PUBLIC

Elfie A. Lacio