

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Edwards County, Sec. 26 Twp. 25s Rge. 16 (W)
 Location as "NE/CNW/SE/SW" or footage from lines C NW NW NW
 Lease Owner Santa-Fe Pipe & Supply, Inc.,
 Lease Name Russell Well No. A-5
 Office Address Box 562, Great Bend, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) oil
 Date well completed May 1 19 59
 Application for plugging filed April 18 19 68
 Application for plugging approved April 18 19 68
 Plugging commenced May 3 19 68
 Plugging completed May 21 19 68
 Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4412' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	326'	none
				5-1/2"	4411'	3562.18'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4412' - 4325' - sand
 4325' - 4285' - 5 sacks cement
 4285' - 300' - mud
 300' - 290' - rock bridge
 290' - 250' - 10 sacks cement
 250' - 215' - 15 sacks cement
 215' - 40' - mud
 40' - 30' - rock bridge
 30' - base - 10 sacks cement

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 24 1968
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc.,
 Address Box 562, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
 T. L. Nutt (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt
 Box 562, Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 22 day of June, 1968

My commission expires July 31, 1970

Mary M. Sweeney
 Notary Public.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NATURAL GAS & OIL
Farm- Russell "A" No. 5

SEC. 26 T. 25 R. 16W
E NW NW

Total Depth. 4412'
Comm. 4-20-59 Comp. 5-1-59
Shot or Treated.
Contractor. Strata Drlg. Co.
Issued. 2-27-60

County Edwards
KANSAS



Elevation. 2062 RB

Production. 166 BOPD

CASING:

8 5/8" 326' cem.w/225 sx.
5 1/2" 441.1' cem.w/125 sx.

Figures Indicate Bottom of Formations.

surface soil & sand	40
sand	190
shale	336
red bed & shale	965
red bed	1035
anhy	1055
shale & shells	1440
shale	1805
shale & lime	2190
lime	2325
lime & shale	2680
shale	2815
shale & lime	2980
chalk, shale & lime	3185
chalk & shale	3310
chalk, lime & shale	3520
lime & shale	3937
lime	4140
lime & shale	4264
lime	4310
lime, shale & sand	4345
lime & shale	4412
Total Depth	
TOPS: Scout	
Heebner	3722
Brown Lime	3860
Lansing	3878
Ft. Scott	4323
Snider	4331
Viola	4371
Base Viola Chrt.	4387

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1968
CONSERVATION DIVISION
Wichita, Kansas

DST #1 Pkr. at 4320'. Total depth 4345'
Open 1 hr. Rec. 735" slgt. mdy. gsy. oil.
Gas to surface in 10 min. 155,000,
15 min. 139,000, 20 min. to small to
gauge. IFP 100 lbs. FFP 272 lbs. BHP
1350 lbs.

DST #2 Pkr. set at 4373'. Total depth
4385'. Tool open 1 hr. Rec. 45" slgt.
oil spkd. mud. IFP 0 lbs. FFP 0 lbs.
BHP 220 lbs.