

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Edwards County, Sec. 26 Twp. 25s Rge. ~~X~~ 16(W)

Location as "NE/CNW/SW" or footage from lines C NW
Lease Owner Santa-Fe Pipe & Supply, Inc.,
Lease Name Russell Well No. A-3
Office Address Box 562, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed March 24 19 59
Application for plugging filed April 18 19 68
Application for plugging approved April 18 19 68
Plugging commenced April 22 19 68
Plugging completed May 2 19 68
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4445 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	323'	none
				5-1/2"	4444'	3394.84'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4445' - 4370' - sand
4370' - 4330' - 5 sacks cement
4330' - 300' - mud
300' - 290' - rock bridge
290' - 190' - 25 sacks cement
190' - 40' - mud
40' - 30' - rock bridge
30' - base - 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc.,
Address Box 562, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
T. L. Nutt (employee or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt
Box 562, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of May, 1968

My commission expires July 31, 1970
Mary M. Guernier
Notary Public.

COPY


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NATURAL GAS & OIL CO.
Farm- Russell "A" No. 3

SEC. 26 T. 25 R. 16W
~~C NW/4~~ C NW/4
~~NE 1/4~~

Total Depth. 4445'
Comm. 3-13-59 Comp. 3-24-59
Shot or Treated.
Contractor. Strata Drlg.
Issued. 8-8-59

County Edwards
KANSAS



Elevation. 2060' RB

Production. 90 BOPD

CASING:

8 5/8" 323' cem w/225 sx.
5 1/2" 4444' cem w/125 sx.

Figures indicate Bottom of Formations.

sand & clay	180
shale	420
red bed	1040
Anhydrite	1067
shale & shells	2058
shale & lime	2430
lime	2465
shale & lime	2640
shale & lime strks	2905
shale & lime	3550
shale chalky	3640
shale & lime	4365
chert & shale	4390
chert	4399
chert, lime & shale	4445
Total Depth	

TOPS: SCOUT

Brown Lime	3877
Lansing	3889
Base Kansas City	4174
Base Ft. Scott	4333
Mississippi Chert	4386
Kinderhook Shale	4404
Kinderhook Sand	4419
Viola	4427

DST #1 packer set at 4332', total depth 4365', tool op 1 hr., recovered 200' oily water, 540' salt water. IFP 100#, FFP 370#. BHP 1340#.

DST #2 packer set at 4368', total depth 4390', tool op 1 hr., recovered 3375' oil. IFP 25#, FFP 695#, BHP 1180#.

Ran Gamma Ray Neutron Log.

Perf. Miss. 4386-90 W/4 shots per ft. Acidized w/500 gal. mud sol.

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1968
CONSERVATION DIVISION
Wichita, Kansas