

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Edwards County, Sec. 26 Twp. 25S Rge. 16 (E) (W) X

Location as "NE/CNW/SW" or footage from lines CNLSW

Lease Owner Leben Drilling, Inc.

Lease Name Russell Well No. 4

Office Address 815 Wichita Plaza Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed 11-8-68 19__

Application for plugging approved 11-9-68 19__

Plugging commenced 11-29-68 19__

Plugging completed 12-13-68 19__

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4422 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	375	None
				5 1/2	None	3208

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Cleaned out cellar.

Sanded to 4330'. Dumped 5 sacks of cement. Working pipe, Shot pipe at 3700'.

Working pipe. Shot pipe at 3600' and 3500'.

Working pipe. Pulling pipe.

Pipe stuck. Working pipe.

Working pipe. Shot pipe at 2500' - 2400' - 2300' and 2230'. Pulling pipe.

Squeezed well with 15 sacks of mud and 85 sacks of cement by Sun Cementing Company.

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1968
CONSERVATION DIVISION
Wichita, Kansas

12-16-1968

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss. J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13 day of December, 1968

My commission expires May 27, 1969

[Signature]
Notary Public.

DRILLER'S LOG


COMPANY R. T. Leeper
 CONTRACTOR L. C. Smitherman Drilling
 FARM RUSSELL #4
 LOCATION C N.L. SE SW SECTION 26-25S-16W
 EDWARDS COUNTY, KANSAS
 COMMENCED 1-15-59
 COMPLETED 5-1-59

0	40	Sand, Shale
40	250	Sand
250	398	Shale
398	670	Shale, Sand
670	1045	Redbed, Shale
1045	1075	Anhydrite
1075	1725	Shale, Shells
1725	2460	Lime, Shale
2460	2950	Lime
2950	3235	Lime, Shale
3235	3335	Lime
3335	3570	Lime, Shale
3570	3840	Lime
3840	3913	Lime, Shale
3913	4383	Lime
4383	4403	Lime, Chert
4403	4422	Lime
	<u>4422</u>	<u>RTD - Set 5½" Casing</u>

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 14 1968
 CONSERVATION DIVISION
 Wichita, Kansas


Set 8 5/8" surface casing @ 375' cemented with 275 sacks of Common

I, James L. Wright, do hereby certify that the above and foregoing is a true and correct copy of the log of the Russell #4 Well, located C N.L. SE SW of Section 26, Township 25 South, Rante 16 West, of Edwards County, Kansas, as reflected by the records of L. C. Smitherman Drilling.


 James L. Wright

STATE OF KANSAS)
 COUNTY OF BARTON) SS

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 12th day of November, 1968.


 Ulanda Nichols