


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Edwards County. Sec. 25 Twp. 25 Rge. 16 (E)W. (W)  
Location as "NE/CNW%SW%" or footage from lines 660' N. and 510' E. of Cen.  
Lease Owner Cities Service Oil Company  
Lease Name Mellon Well No. 1  
Office Address Box 308, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed August 15 19 62  
Application for plugging filed September 3 19 65  
Application for plugging approved September 8 19 65  
Plugging commenced September 22 19 65  
Plugging completed September 23 19 65  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production September 12 19 65  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving  
Producing formation Cherty Conglomerate Depth to top 4313 Bottom 4329 Total Depth of Well 4459 Feet  
Show depth and thickness of all water, oil and gas formations. P. B. T. D. 4421'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	373'	None
				5-1/2"	4458'	2378'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4421-4400', heavy mud.  
4400-4265', 5 sx cement.  
4265- 315', heavy mud.  
315- 280', bridge at 315', 20 sx cement.  
280- 40', mud.  
40' to base of cellar, 10' rock, 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
W. J. Devaney (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Devaney  
Box 308, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of September, 1965

My commission expires Dec. 6, 1966

W. M. McFarland  
Notary Public.

# WELL RECORD

Company Cities Service Petroleum Co. Well No. 1 Farm Mallon  
 Location 660' North and 510' East of Center Sec. 25 T. 25 R. 16W  
 Elevation 2058 KF, 2055 DF, 2050 Gr. County Edwards State Kansas  
 Initial Prod. Potential 51 oil, 5 water, 24 hrs., 8-15-62 Contractor Leben Drlg., Inc.  
~~Acid~~ Frac 5000# sand & 5000 gals. oil 7-19-62 Drlg. Comm. 6-28-62  
 T.D. 4459' P.B.T.D. 4421' Drlg. Comp. 7-10-62

Casing Records:

8-5/8" at 373' with 250 sacks cement.  
 5-1/2" at 4458' with 200 sacks cement.

Formation Record:

sand and shale	0-373
red bed and shale	1080
anhydrite	1105
shale	2010
shale and lime	2215
lime and shale	2690
shale and lime	2830
lime and shale	3075
lime	3295
lime and shale	3523
lime	3776
shale and lime	3844
lime	4195
lime and shale	4250
lime	4340
Conglomerate	4382
lime	4400
shale	4438
lime	4469

4469 Rotary T.D.=4459 S.L.M. from ground level.

Slope Tests (Syfo):

1000' - 1°  
 2010' - 1°  
 2505' - 1/2°

**RECEIVED**  
 STATE CORPORATION COMMISSION

SEP 8 1965

CONSERVATION DIVISION  
 Wichita, Kansas