

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-00372-0000

LEASE NAME Curtis

WELL NUMBER #2

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 24 TWP 25 RGE 16 (E) or (W)

COUNTY Edwards

Date Well Completed 8-7-59

Plugging Commenced 8-29-91

Plugging Completed 9-16-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS Box 8647, Wichita, Ks. 67208

PHONE # 316-672-6373 OPERATORS LICENSE NO. 8061

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 16, 1991 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 4410'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

SEP 19 1991

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 357' | None |
| | | | | 5-1/2" | 4400' | 2,754.41' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped sand to 4250' and 5 sacks cement. Shot casing at 3817', 3531', 3209', 3023' & 2742'. Pulled 84 joints of 5-1/2" casing. Halliburton plugged well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls and 125 sacks 60/40 pozmix with 6% gel. Maximum pressure was 400 psi and shutin 150 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. of Kansas

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1991

Jonas M. Leatherman
Notary Public

My Commission Expires

