

SP

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1966
CONSERVATION DIVISION
Wichita, Kansas

1-31-1966

Operator's Full Name Shawver Armour, Inc.

Complete Address: 817 Central Bldg., Wichita, Kansas

Lease Name English Well No. # 1

Location NE NE SW Sec. 29 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 3950'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Shawver Armour Drilling, Inc.

Address: 817 Central Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 11:00AM Day 28th Month Jan. Year 1966

The Above well was plugged as follows:

313' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid
in the hole was at 80'. 1st cementing plug and 1/2 sack of hulls was
pushed in fluid to 275', and cemented with 25 sacks, through the drill
pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged solid with dry cement and hulls on fluid, and cemented with
10 sacks to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1-31-66

INV. NO. 2625-1A