

Form GP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSIONAUG 20 1963  
8-20-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Western Petroleum Co. Inc.

Complete Address: 925 Patton Road, Great Bend, Kansas

Lease Name Boylan "A" Well No. # 1

Location C SE NW Sec. 30 Twp. 25 Rge. 14 (E)  (W) W

County Stafford Total Depth 4400

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A X

Other well as hereafter indicated:

Plugging Contractor: Strata Drilling Inc.

Address: Box 355, Great Bend, Kansas License No.

Operation Completed: Hour 2:00AM Day 17th Month August Year

The Above well was plugged as follows:

313' of 8 5/8" surface pipe, cement circulated. Fluid level was up in

the hole. 1 sack hulls and 1st cementing plug was pushed to 305', and

cemented through drill pipe with 25 sacks cement. Hole was filled

with mud to 40', 2nd cementing plug, 1 sack hulls, cemented with 15

sacks to base cellar. Ra t hole bridged and cemented with 2 sacks,

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/30/63INV. NO. 7630-WSigned: Archie Elving  
Well Plugging Supervisor