

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

SEP 28 1964

CONSERVATION DIVISION  
Wichita, Kansas

9-28-1964

15-047-00068-0000

Operator's Full Name Morgenstern & Spector

Complete Address: Box 661, Russell, Kansas

Lease Name McClanahan Well No. # 1

Location SE/4 Sec. 2 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 4846

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Company

Address: Route 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 9:45AM Day 27th Month Sept. Year 1964

The Above well was plugged as follows:

288' of 8 5/8" surface pipe, cement circulated. 4845' of 5 1/2" long string,  
cemented with 75 sacks. All perforations had been squeezed. Bottom of the  
hole was sanded to 4830', and cemented with 5 sacks. Water was up in the  
hole. Bridge plug was set at 270', and 10' of rock bridge. 8 sacks of cem-  
ent was mixed in a barrel, and put on top of bridge at 260', through dump  
bailer, and let set over-night. Next morning hole was bailed dry, and 17  
sacks of cement added to plug. Hole was filled with mud to 40', and 10' of  
rock bridge, and cemented with 10 sacks to the base of the cellar. 2820' of  
5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/28/64

INV. NO. 9881-u

Signed: Archie Elving  
Well Plugging Supervisor