

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -047-26311-0000 (of this well)

Operator's Full Name Rupe Oil Co.

Complete Address Box 2273, 434 Ohio, Wichita, Ks. 67201

Lease Name Miller Well No. 1

Location C NE SW SE Sec. 5 Twp. 26s Rge. 18 (E) (W) X

County Edwards Total Depth 4742

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Glenn's Casing Pulling.

Address Box 413, Ellinwood, Ks. 67526 License No. 832

Operation Completed: Hour 10:15 Am. Day 16 Month 4 Year 1980

The above well was plugged as follows:

331' 8 5/8" casing w/300 sax cement. 4 1/2" casing set at 4741' w/150 sax  
cement. Perforated at 4689' - Sand back to 4650' - Top sand w/4 sax mixed  
cement w/ dump bailer. Pull 2845' casing. Howco mixed & pumped in  
8 5/8" casing 8 sax hulls - 25 sax gel - 125 sax 50/50 posmix cement  
w/4% gel & 3% cc to top of casing. Shut in w/500# pressure.

RECEIVED  
STATE CORPORATION COMMISSION

APR 21 1980 4-21-1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 4-21-80

INV. NO. (966-a)