

J KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed February 1, 1967

2-3-1967
RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Glenn N. Rupe 15-047-00134-0001

Complete Address: 222 Brown Bldg., Wichita, Kansas

Lease Name Newsom "A" Well No. # 1

Location C S/2 NE SE Sec. 11 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 3528'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Gabbert-Jones, Inc.

Address: 830 Sutton Place, Wichita, Kansas License No.

Operation Completed: Hour 2:30PM Day 1st Month Feb. Year 1967

The Above well was plugged as follows:

328' of 8 5/8" surface pipe, cement circulated. Fluid level in the hole
was at 133'. 1st cementing plug and 1/4 sack of hulls was pushed in fluid
to 280', and cemented with 25 sacks, through the drill pipe at 280'.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to
the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 2/3/67
INV. NO. 4715-4