

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

1-11-1965

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Western Petroleum Co., Inc. 15-047-16063-00-01

Complete Address: Box 65, Great Bend, Kansas

Lease Name Newsom Well No. # 1

Location C SW NE Sec. 11 Twp. 26 Rge. 18 (E) (W)W

County Edwards Total Depth 3365'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: This was a wash down

Plugging Contractor: Western Petroleum Co., Inc.

Address: Box 65, Great Bend, Kansas License No. _____

Operation Completed: Hour 8:00AM Day 10th Month Jan. Year 1965

The Above well was plugged as follows:

283' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid
level in the hole was at 200'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 275', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1-12-65

INV. NO. 506-W