

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-10018-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 18-30S-8W  
3630 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: MESSENGER D Well #: 3-18  
County: KINGMAN Total Vertical Depth: 4324 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4319	2809	170 SX
SURF	8.625	408		275 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/28/2015 12:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/30/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP @ 4202' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2809' PULLED CASING. RAN TUBING INTO 1325' LOADED HOLE WITH 300 LBS OF MUD, SPOTTED 35 SX OF CEMENT AND 100 LBS OF HULLS. PULLED TUBING TO 879' SPOTTED 35 SX OF CEMENT. PULLED TUBING TO 440' CIRCULATED TO SURFACE WITH 185 SX OF CEMENT. CEMENT FELL BACK 90' TOPPED OFF WITH 15 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4257	4271		

Received  
KANSAS CORPORATION COMMISSION  
OCT 28 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: CEMENT ALLIED FROM RUSSELL KS. DENIED TA LOST LEASE.

Plugged through: TBG

11/4/15CPM

District: 02 Signed B. J. Hope (TECHNICIAN)

✓