

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-20591-00-00  
Spot: NENE Sec/Twnshp/Rge: 5-18S-8W  
4620 feet from S Section Line, 660 feet from E Section Line  
Lease Name: ROLFS 18-8 Well #: 2-5  
County: RICE Total Vertical Depth: 1550 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1550		
PROD	4.5	1550		75 SX
SURF	8.265	203		100 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/13/2015 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: According to the rules and regulations of the KCC

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/13/2015 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 800' AND 260'. RUN TUBING TO 1350' AND PUMP 35 SX'S WITH 2% CC & 100 #'S COTTON HULLS. PULL TUBING TO 800' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 260' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
1511	1514	CSG	
1325	1328	CSG	
1297	1300	CSG	
1278	1281	CSG	
1265	1393	CSG	

Received  
KANSAS CORPORATION COMMISSION  
OCT 28 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS #8599. COPELAND TICKET #43188.

Plugged through: TBG

District: 02

Signed: Virgil Clothier  
(TECHNICIAN)

11/4/15 ckm