

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22428-00-00
Spot: N2S2SESE Sec/Twnshp/Rge: 1-19S-9W
540 feet from S Section Line, 660 feet from E Section Line
Lease Name: COLBERG 19-9 Well #: 1-1
County: RICE Total Vertical Depth: 3510 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	1950		
CIBP	5.5	2400		
PROD	5.5	3496		180 SX
SURF	8.625	282		185 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/12/2015 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE WitnessType: NONE
Date/Time Plugging Completed: 10/12/2015 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. CIBP'S HAD BEEN PREVIOUSLY SET BY FOUNDATION ENERGY MGMT @ 2400', 1950' AND 1400' AND CAPPED WITH 2 SX'S EACH. PERFORATE AT 1200', 800', AND 330'. RUN TUBING TO 1200' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 800' AND PUMP 35 SX'S, PULL TUBING TO 330' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF WITH 15 SX'S.

Perfs:

Top	Bot	Thru	Comments
3377	3382	CSG	
3350	3354	CSG	
3132	3138	CSG	
3108	3114	CSG	
3088	3094	CSG	
3082	3084	CSG	
3068	3072	CSG	
2998	3002	CSG	
2994	3032	CSG	
2950	2954	CSG	
2792	2801	CSG	
2464	3382	CSG	
2445	2454	CSG	

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS. #8597. COPELAND #43271.

Plugged through: TBG

11/4/15

District: 02

Signed Virgil Clothier
KCC WICHITA (TECHNICIAN)

NOV 02 2015
RECEIVED

Handwritten initials