

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-20150-00-02
Spot: NESENW Sec/Twnshp/Rge: 4-34S-2E
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: FERGUSON Well #: 1
County: SUMNER Total Vertical Depth: 3845 feet

Operator License No.: 4699
Op Name: PHILLIPS OIL PROPERTIES INC.
Address: 733 N. BALTIMORE
DERBY, KS 67037

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2890		
PROD	4.5	3050		150 SX
SURF	8.625	219		165 SX
SURF	2.375	2880	2880	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2015 9:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: TROY PHILLIPS Company: PHILLIPS OIL PROPERTIES, INC. Phone: (316) 295-4335

Proposed Plugging Method: AS PER KCC RULES AND REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 09/24/2015 7:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP SET @ 2890', TAGGED TOP OF CEMENT WITH WIRELINE @ 2880' RAN IN WITH TUBING AND CIRCULATED 75 SX OF 60/40 POS MIX WITH 4% AND 3% POLYFLAKE, RAN BACK IN AND TAGGED TOP OF CEMENT @ 2360' PULLED TUBING TO 300' AND PERFORATED THERE, CIRCULATED 110 SX OF CEMENT TO SURFACED, LET IT SET AND TOPPED OFF AGAIN WITH 20 SX. PLUGGING COMPELTE. CONSOLIDATED OIL WELL SERVICES, LLC OUT OF ELDRADO KS. TICKET #46214. -- NO ORDER WAS ISSUED, OPERATOR RESPONDED AFTER NOV LETTERS THAT WERE SENT AND OPERATOR HAD A CONVERSATION WITH DIST. SUPERVISOR.

Perfs:

Top	Bot	Thru	Comments
2948	2955	CSG	
2806	2814		

Remarks: WELL(S) WERE PLUGGED DUE TO KCC'S RESPONSE TO LANDOWNER COMPLAINT.

Plugged through: TBG

District: 02

Signed _____
KCC WICHITA
NOV 02 2015
RECEIVED

11/4/15 ckm
KCC WICHITA
NOV 02 2015
RECEIVED