

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-013-20033-00-00
Spot: NWNWNW **Sec/Twnshp/Rge:** 32-1S-17E
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: WILSON **Well #:** 1
County: BROWN **Total Vertical Depth:** 5761 feet

Operator License No.: 33652
Op Name: W. T. W. OPERATING, LLC
Address: 1804 ROLLINGWOOD CT.
BEDFORD, TX 76021

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1865		
CIBP		2265		
CIBP		2678		
CIBP		4480		
COND	13.375	80		
PKR	2.875	5350		
PROD	5.05	5765		300 SX
SURF	12.875	392		268 SX
T1	2.875	5410		

Well Type: GAS **UIC Docket No:** **Date/Time to Plug:** 10/14/2015 8:00 AM
Plug Co. License No.: 5721 **Plug Co. Name:** GLACIER PETROLEUM CO., INC.
Proposal Rcvd. from: BILL WAGGONER **Company:** W.T.W. OPERATING, LLC **Phone:** (682) 503-4046

Proposed Plugging Method: Place a total of five cement plugs in open hole once the current 5 1/2" casing above the 1,865' plug is removed. Each plug is to be 50' in length. and will be placed opposite the formations listed below: If the 5 1/2 casing cannot be pulled from the well, Each zone will be perforated and squeezed with sufficient cement to cover the fifty foot interval mentioned below:
 The top 50 feet of the Marmaton formation 1220'
 The lower 50" of the base of the KC @ 1168" and the top 50" of the KC @ 952"
 The top 50 feet of the Lansing @ 850"
 The 50 feet at the bottom of the surface casing at 392 feet including the lower ten feet of cement into the surface casing at the bottom
 THE ABOVE METHOD WAS DISCUSSED IN PERSON WITH THE FIELD REPRESENTATIVES IN THE CHANUTE FIELD OFFICE ON AUG 24Y2015.

Plugging Proposal Received By: TAYLOR HERMAN **Witness Type:** NONE
Date/Time Plugging Completed: 10/15/2015 8:00 AM **KCC Agent:** TAYLOR HERMAN

Actual Plugging Report:

CIBP SET AT 1845'. PARTED AND PULLED 1236' OF THE 5.5" PRODUCTION CASING. RAN IN 1220' OF 2 3/8" TUBING AND PUMPED 15 SACKS OF CEMENT. PULLED THE TUBING UP TO 948' AND PUMPED 15 SACKS OF CEMENT. PULLED THE TUBING UP TO 442' AND PUMPED 35 SACKS OF CEMENT. PULLED THE TUBING UP TO 64' AND PUMPED CEMENT TO THE SURFACE.

RECEIVED
 KCC DIST # 3
 OCT 29 2015
 CHANUTE, KS

TH

Perfs:

Top	Bot	Thru	Comments
5673	5683		
5592	5596		
5540	5546		
5518	5528		
5458	5462		
5419	5425		
5222	5228		
5143	5153		
4916	4924		
4744	4754		
3480	3486		
2690	2696		
2275	2280		
1900	1905		

Remarks:

Plugged through: TBG

Received
 KANSAS CORPORATION COMMISSION

11-2-15 NOV 02 2015 11/4/15 ckm

CONSERVATION DIVISION
 WICHITA, KS

District: 03

Signed

Taylor C. Herun
(TECHNICIAN)

Form CP-2/3

Received
KANSAS CORPORATION COMMISSION

NOV 02 2015

CONSERVATION DIVISION
WICHITA, KS