

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-30397-00-00**Spot:** SWNESWSE**Sec/Twnshp/Rge:** 25-33S-15E713 feet from S Section Line, 1771 feet from E Section Line**Lease Name:** KLUMP**Well #:** 25-1**County:** MONTGOMERY**Total Vertical Depth:** 1215 feet**Operator License No.:** 5817**Op Name:** BENSON MINERAL GROUP, INC.**Address:** 1560 BROADWAY STE 1900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	45		8 SX

Well Type: DH**UIC Docket No:****Date/Time to Plug:** 07/30/2015 12:00 AM**Plug Co. License No.:** 32884**Plug Co. Name:** ELMORE'S, INC.**Proposal Rcvd. from:** KODIAK CONSTRUCTION **Company:****Phone:** (620) 505-0479

Proposed Plugging Method: Run 1" tubing to TD. Put 5 sacks of cement up to half point of well. Add 5 more sacks. Go up to 350' and cement surface

Plugging Proposal Received By: DUANE SIMS**Witness Type:** COMPLETE (100%)**Date/Time Plugging Completed:** 07/30/2015 12:00 AM**KCC Agent:** DUANE SIMS**Actual Plugging Report:****Perfs:**

Well had no production casing in it. Surface casing only well. Ran 1" to 992' gelled hole and spotted 10 sack plug. Pulled up to 700' and spotted 10 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 80 sacks of cement were used to plug this well.

RECEIVED
KCC DIST # 3

OCT 20 2015

CHANUTE, KS

DS

KCC WICHITA

OCT 26 2015

RECEIVED

10-26-15

Remarks:**Plugged through:** TBG**District:** 03**Signed** **(TECHNICIAN)**

10/27/15 CKM