

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-10000-00-01
Spot: SENWNENE Sec/Twnshp/Rge: 3-24S-41W
4648 feet from S Section Line, 728 feet from E Section Line
Lease Name: BOLTZ A Well #: 1
County: HAMILTON Total Vertical Depth: 2370 feet

Operator License No.: 9081
Op Name: BRECK OPERATING CORP.
Address: 300 N BRECKENRIDGE PO BOX 911
BRECKENRIDGE, TX 76424

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2356	0	WITH 150 SX CMT
SURF	10.75	699		WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/30/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: GARLAND (BUB) SMITH Company: CONSULTANT Phone: (620) 384-6914

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2015 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

THERE IS A 2 3/8" SIDE STRING DISPOSAL STRING SET AT 1157' WITH 500 SX CMT. (TOC BY TEMP SURVEY WAS 490'). STRING WAS PLUGGED ON 4/28/86.
PUMP 100 SX CMT WITH 150# HULLS DOWN 4 1/2" CASING. DISPLACE CMT TO 950' & TEST CASING TO 600 SPI. HOLDING. PERFORATE 4 HOLES AT 350'.
ATTEMPT TO PUMP INTO PERFS AT 950 PSI. COULD NOT. RUN TBG TO 814' & CIRCULATE CMT TO SURFACE USING 65 SX CMT. TOOH WITH TBG & TOP OFF WITH 5 SX CMT. PUMP 5 SX CMT DOWN THE ANNULUS & PRESSURE TO 300#.

KCC WICHITA
OCT 20 2015
RECEIVED

10-20-15

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

10/27/15 ckm

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
OCT - 7 2015
KCC DODGE CITY