

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23149-00-00  
Spot: SENENW Sec/Twnshp/Rge: 15-7S-19W  
4240 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: BURTON Well #: 3  
County: ROOKS Total Vertical Depth: 3445 feet

Operator License No.: 6569  
Op Name: CARMEN SCHMITT, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3438		160 SX
SURF	8.625	260		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2015 10:30 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Production perforations: 3144' - 3337'  
DT Tool at 1481' w/375 sx cement

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/06/2015 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3107' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2524' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1521' and pumped 80 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 10 sx cement. Shut in pressure 200 psi.

GPS: 39.44901N -099.42708W

Perfs:

Top	Bot	Thru	Comments
3357	3361		
3331	3337		
3310	3314		
3258	3262		
3246	3250		
3219	3223		
3200	3202		
3160	3166		
1490	1491		

Remarks: COPELAND ACID AND CEMENT TICKET # 43184

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

OCT 07 2015

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 15 2015

CONSERVATION DIVISION  
WICHITA, KS

10/27/15 CKM